

City of Tawas City

Storm Sewer Maintenance and Improvement Plan

	2020-2021	2021-2022	2022-2023	2023-2024	2024-2025
DESCRIPTION OF WORK					
First Street between Harris and 12th Avenue: Replace existing cross tube with 40 LF of 12" Dual wall HDPE pipe. Project also requires approximately replacement of 220 sq ft of asphalt.	X				
Eleventh Avenue between Harris and North Street: Install approximately 460 LF of 6" Dual wall HDPE pipe on the west side of Eleventh and replace approximately 40LF of crosstube with 12" Dual wall HDPE pipe under Eleventh to the East at Harris. This project will include 4 new catch basins. (1)24" basin and (3)18" basins	X				
Fourth Street Between Seventh and Eight Avenues: Install approximately 300 LF of 6" Dual wall HDPE pipe on the north side of the street. This project will include 1 new 18" catch basin.	X				
Sixth Avenue between North and First Streets: Install approximately 540 LF of 12" Dual wall HDPE pipe on the west side of the street and 340 LF of 12" Dual wall HDPE pipe on the East side of the street. This project will include 6 new 24" catch basins. 3 on each side of the street. NOTE: Actual LF of pipe may change depending on elevations and condition of existing driveway tubes.		X			
Third Avenue between North and First Streets: Install approximately 600 of 12" Dual wall HDPE pipe on the west side of the street and 300 LF of 12" pipe on the east side of the street. This project will include the installation of 4 new 24" catch basins, 2 on each side of the street.			X		
River Street between Jefferson and Birch Streets: Install new 12" Dual wall HDPE crosstube under River Street at Jefferson, then 640 LF of 12" Dual wall HDPE pipe on the west side of River and 370 LF on the east side. The east side of river will have a 12" lateral line running to the east from the intersecting area near Vine Street approximately 250'. This project will include 6 new 24" catch basins, 3 on each side of the street.				X	
Victoria Lane between Hemlock Rd. and Roberta Drive: Replace existing concrete pipe Storm Sewer with 1250 LF of 12" Dual wall pipe on the East Side of the Street. This project will include 6 new 24" catch basins, tree removal, and replacement of residential asphalt driveways.					X

Drainage Plan

- 2020-2021
- 2021-2022
- 2022-2023
- 2023-2024
- 2024-2025

