

City of Tawas City

Water Distribution System Improvements and Maintenance

Updated January 2020

	2019/20	2020/21	2021/22	2022/23	2023/24	2024/25	2025/26	2026/27	2027/28	2028/29	2029/30	2030/31	2031/32	2032/33	2033/34	2034/35	2035/36	2036/37	2037/38	2038/39	2039/40
Project Design or Preparation																					
Design Sixth Avenue and Whittemore Street water main replacement	X																				
Design Lake Street (US-23) water main replacement from Tawas River to Bay Drive				X																	
Design Bay Drive water main replacement from Lake Street (US-23) to Townline Road				X																	
Design Twelfth Avenue water main installation from water tower to Lake Street																	X				
Projects																					
Fourth Avenue/First Street water main replacement																					
<ul style="list-style-type: none"> replace existing 4-inch cast iron water main on Fourth Avenue from Whittemore Street to Second Street replace existing 2-inch cast iron water main on Fourth Avenue from Second Street to First Street replace existing 2-inch cast iron water main on First Street from Third Avenue to Fourth Avenue 																					
Replace hydrant #6100 at 1045 Bay Drive																					
Sixth Avenue and Whittemore Street water main replacement		X																			
<ul style="list-style-type: none"> replace existing 4-inch cast iron water main on Sixth Avenue from Second Street to Whittemore Street with 8-inch C900 water main install 8-inch C900 water main on Sixth Avenue from Whittemore Street to Mathews Street replace existing 4-inch cast iron water main on Whittemore Street from Fifth Avenue to Sixth Avenue with 8-inch C900 water main 																					
Lake Street (US-23) water main replacement							X														
<ul style="list-style-type: none"> replace existing water main with 12-inch water main from 616 West Lake Street (Post Office) to the water tower in conjunction with MDOT project to reconstruct US-23 																					
Lake Street (US-23) water main replacement (Phase 1)									X												
<ul style="list-style-type: none"> replace existing 6-inch cast iron water main on Lake Street beginning at Ninth Avenue continuing southwest approximately 1,350 feet ending at 1029 West Lake Street 																					
Lake Street (US-23) water main replacement (Phase 2)											X										
<ul style="list-style-type: none"> replace existing 6-inch cast iron water main on West Lake Street beginning at 1029 West Lake Street and continuing southwest approximately 1,350 feet ending at 1127 Bay Drive 																					
Lake Street (US-23) water main replacement (Phase 3)													X								
<ul style="list-style-type: none"> replace existing 6-inch cast iron water main on Lake Street beginning at 1127 Bay Drive and continuing southwest approximately 1,350 feet ending at the intersection of Bay Drive and Townline Road 																					
Twelfth Avenue water main installation																					
<ul style="list-style-type: none"> install 12-inch water main from water tower through 120 acres along Twelfth Avenue to Lake Street to loop distribution system 																		X			

Water Distribution Improvements

- 2020-2021
- 2021-2022
- 2022-2023
- 2023-2024
- 2024-2025

