

City of Tawas City

Wastewater Collection System Improvements and Maintenance

Updated January 2022

	2022-23	2023-24	2024-25	2025-26	2026-27	2027-28	2028-29	2029-30	2030-31	2031-32
DESCRIPTION OF WORK/LOCATION										
Load Bank Test Generators	1,500			1,800			2,000			2,250
Second Avenue Crane Inspection	200	200	200	225	225	225	225	225	225	225
PIPE WORK BETWEEN MANHOLES										
MH 315-316 dig and repair tap 122' from MH 315					1,000					
MH 427-428 dig and repair 167' from MH 427										1,000
MH 424-424 DE dig and repair broken cap 562' from MH 424										1,000
MH 424 DE install manhole										9,500
MANHOLE WORK										
MH 417 Rehab, Frame and Cover	800									
MH 405 Rehab, Frame and Cover	800									
MH 402 Rehab, Frame and Cover	800									
MH 413 Rehab, Frame and Cover, 1 row of blocks	925									
MH 412 Rehab, Frame and Cover, 1 row of blocks	925									
MH 404 Rehab, Frame and Cover, 1 row of blocks	925									
MH 11 Rehab, Frame and Cover		800								
MH 10 Rehab, Frame and Cover		800								
MH 14 Rehab, Frame, Cover and Line 6'		2,240								
MH 13 Rehab, Frame, Cover and Line 7'		2,480								
MH 624A Rehab			350							
MH 615 Rehab			350							
MH 60 Rehab, Frame and Cover			800							
MH 53 Rehab, Frame and Cover, 2 rows of blocks			1,075							
MH 545 Rehab, Frame and Cover				800						
MH 546 Rehab, Frame and Cover				800						
MH 208 Rehab, Frame and Cover				800						
MH 12 Rehab, 1 row of blocks				925						
MH 213 Rehab, Frame and Cover, 1 row of blocks				925						
MH 3 Rehab, Frame and Cover, 2 rows of blocks				1,075						
MH 27 Rehab, Frame and Cover					875					
MH 28 Rehab, Frame and Cover					875					
MH 314 Rehab, Frame and Cover, 1 row of blocks					925					
MH 427 Rehab, Frame and Cover, 1 row of blocks					1,000					
MH 315 Rehab, Frame and Cover, MDOT casting					1,000					
MH 316 Rehab, Frame and Cover, MDOT casting					1,000					
MH 44 Rehab, Frame and Cover, 1 row of blocks					1,000					
MH 424 Rehab, Frame and Cover, 3 rows of blocks					1,500					
MH 305 Rehab, Frame and Cover						1,000				
MH 306 Rehab, Frame and Cover						1,000				
MH 426 Install Gasketed 1060 cover										400
MH 44A Rehab, Frame and Cover, 1 row of blocks										1,200
MH 217 Rehab, Frame and Cover, 1 row of blocks										1,200
LIFT STATION IMPROVEMENTS/MAINTENANCE										
Install Bypass at Industrial Avenue LS	20,000									
Line (2) Wet Wells at Industrial Avenue LS	22,000									
Line First Avenue LS Wet Well		19,000								
Line Second Avenue LS Wet Well		19,000								
Line Wet Well at Bay Drive LS			16,500							
Replace Pumps and Panel at M-55 LS				40,000						
Bay Drive LS Rehabilitation					75,000					
First Avenue LS Rehabilitation						80,000				
Wet/Dry Well and Station Rehabilitation*			560,000							
Second Avenue LS Rehabilitation*									860,000	
Industrial Avenue LS Rehabilitation*										331,000
TOTAL OF PROJECTS IDENTIFIED FOR EACH YEAR	48,875	44,520	579,275	47,350	84,400	82,225	2,225	225	860,225	347,775

*Full projects are described in SAW Grant CIP Plans