City of Tawas City
Storm Sewer Maintenance and Improvement Plar
Updated January 2022

DESCRIPTION OF WORK	2022-2023	2023-2024	2024-2025	2026-2027	2027-2028	2028-2029	2029-2030	2030-2031	2031-2032
First Street between Harris and 12th Avenue: Replace existing cross tube with 40 LF of 12" dual wall HDPE pipe. Project also requires replacement of approximately 220 sq ft of asphalt.	X								
Third Avenue between North and First Streets: Install approximately 600 of 12" dual wall HDPE pipe on the west side of the street and 300 LF of 12" pipe on the east side of the street. This project will include the installation of 4 new 24" catch basins, 2 on each side of the street.	X								
River Street between Jefferson and Birch Streets: Install new 12" dual wall HDPE crosstube under River Street at Jefferson, then 640 LF of 12" dual wall HDPE pipe on the west side of River Street and 370 LF on the east side. The east side of River Street will have a 12" lateral line running to the east from the intersecting area near Vine Street, approximately 250'. This project will include 6 new 24" catch basins, 3 on each side of the street.		X							
Victoria Lane between Hemlock Rd. and Roberta Drive: Replace existing concrete pipe storm sewer with 1,250 LF of 12" dual wall pipe on the east side of the street. This project will include 6 new 24" catch basins, tree removal, and replacement of residential asphalt driveways.			X						
Woodward Avenue between West Lake Street and Margo Street: Clean ditch.					X				
Bay Drive beginning at the intersection of West Lake Street south to 1127 Bay Drive: Replace old storm sewer with approximately 800 feet of 12" dual wall HDPE pipe on the west side of the street.							X		
Bay Drive beginning at 1127 Bay Drive south to the intersection of Townline Road: Replace old storm sewer with approximately 1,460 of 12" dual wall HDPE pipe on the west side of the street.									X