

Updated March 2025

[illegible]

City of Tawas City
Water Distribution System Improvements and Maintenance
Updated March 2025

	2025/26	2026/27	2027/28	2028/29	2029/30	2030/31	2031/32	2032/33	2033/34	2034/35	2035/36	2036/37	2037/38	2038/39	2039/40	2040/41	2041/42	2042/43	2043/44	2044/45	2045/46
Project Design or Preparation																					
Design Lake Street (US-23) water main replacement from Tawas River to Bay Drive	X																				
Design Bay Drive water main replacement from Lake Street (US-23) to Townline Road	X																				
Design Bay Street (US-23) primary water main installation through East Tawas	X	X																			
Design Wheeler Street water main installation from Court Street to dead end			X																		
Design Twelfth Avenue water main installation from water tower to Lake Street											X										
Projects																					
Lake Street (US-23) water main replacement <ul style="list-style-type: none">replace exsiting water main with 12-inch water main from 616 West Lake Street (Post Office) to the water tower in conjunction with MDOT project to reconstruct US-23	X	X																			
Bay Street (US-23) in East Tawas primary water main installation <ul style="list-style-type: none">install new 12-inch primary water main along US-23 in East Tawas from Tawas Beach Road to the pit meter next to 707 East Lake Street in conjunction with MDOT project to reconstruct US-23		X	X																		
Wheeler Street water main abandonment <ul style="list-style-type: none">move connection for Tawas Pharmacy located at 306 West Lake Street to Court Street behind the buidngabandon the existing 2-inch cast iron water main on Wheeler Street from West Lake Street to Court Street		X	X																		
Wheeler Street water main installation <ul style="list-style-type: none">install new 6-inch water main on Wheeler Street beginning at the intersection of Court Street and continuing approximately 320 feet north west to the dead end at the Tawas Riveradd a hydrant at the end of Wheeler Street					X																
Lake Street (US-23) water main replacement (Phase 1) <ul style="list-style-type: none">replace existing 6-inch cast iron water main on Lake Street beginning at Ninth Avenue continuing soutwest approximately 1,350 feet ending at 1029 West Lake Street						X															
Lake Street (US-23) water main replacement (Phase 2) <ul style="list-style-type: none">replace existing 6-inch cast iron water main on West Lake Street begnning at 1029 West Lake Street and continuing southwest approximately 1,350 feet ending at 1127 Bay Drive								X													
Lake Street (US-23) water main replacement (Phase 3) <ul style="list-style-type: none">replace existing 6-inch cast iron water main on Lake Street beginning at 1127 Bay Drive and continuing southwest approximately 1,350 feet ending at the intersection of Bay Drive and Townline Road										X											
Twelfth Avenue water main installation <ul style="list-style-type: none">install 12-inch water main from water tower through 120 acres along Twelfth Avenue to Lake Street to loop distribution sytemobtain utility easement at the end of Margo Street to 120-acre property for main looping													X								
Third Avenue and Second Street water main replacement <ul style="list-style-type: none">replace existing 6-inch cast iron water main on Third Avenue from First Street to Whitmore Street and on Second Street from Third Avenue to Fourth Avenue																X					